BANGALORE DIVISION.

Notification, dated 4th August 1933.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Bangalore Division, up to 2 P.M. on 28th August 1933, for Restoring of Korati Urumundinakere Reg. No. 15—626 of Hoskote Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1934.

The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office, Bangalore Division, Bangalore, between the hours of 11 A.M. and 5 P.M. on all office days.

3. Tenders should be submitted on printed forms, which may be obtained from the Executive Engineer. They should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees three hundred as earnest money and be superscribed "Tender for Restoring of Korati Urumundinakere Reg. No. 15—626 of Hoskote Taluk" in default of which, tenders will be rejected.

5. The final acceptance of any tender, will rest with the Executive Engineer who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted, will be posted in the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Charges on account of scaffolding materials, implements for setting out, barricading, clearing site, supply of water, etc., that may be found necessary during execution will not be paid for separately, but should be borne by the contractor.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of disputes about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer, Bangalore Division, will be final and legally binding.

12. Quotations must be shown in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotations quoted at so much percentage less or more than estimate rate will not be accepted.

13. Any tender containing a conditional clause contrary to these requirements or making stipulations not provided for either in this advertisement or the abstract quantity will summarily be rejected.

Abstract quantities for Restoring of Korati Urumundinakere Register No. 15—626 of Hoskote Taluk.

Sl. No.	Description of work	Unit	Quantity
	BUND R. L. 57·00 TOP WIDTH 4½ FEET.		
1	Clearing Jungle	Grade	22
2	Cutting steps and grips	,,	22
3	Earthwork raising bund including watering and tamping lead and lift, etc., complete.	C.yds.	7140
4	New stone revetment with jelly backing and wedging	,,	796
5	Old stone work removing and resetting with new jelly.	,,	522
6	Turfing with lead watering and tamping ...	Sqr.	6095
7	Removing and refixing grade stones with numbering and fixing complete.	No.	18
8	Do do Index stones	,,	18
9	Do do B. M. stones	,,	2
10	Do do Reg. No. stones	,,	1

Sl. No.	Description of work	Unit	Quantity
11	Supplying and fixing new grade stones ..	No.	6
12	Do Index stones ...	,,	6
	WASTE WEIR R. L. 52 00 75 FEET LONG.		
1	Earthwork excavation	C.yd.	10
2	Burnt brick in surki mortar	C.ft.	595
3	Removing and resetting the existing slab in surki mortor.	S.ft.	107
4	New burnt stone slabs 6" thick dressed and fixed in surki mortar.	Sqr.	23
5	Plastering with surki mortar	,,	5·70
6	Rough stone revetment with wedging for wings with lead two miles.	C.yds.	17
7	Joggle stones	,,	27
8	Rough stone apron with wedging and lead 2 miles ...	,,	27
9	Pin slabs	Each	3
10	Providing surki concrete ramp and plastering, etc., complete.	C.ft.	375
	OPENING A NEW WEIR DRAFT CHANNEL.		
1	Earthwork excavation and using the stuff to the training bund to the left with lead.	C.yd.	3316·43
2	New rough stone revetment work with jelly backing and wedging.	,,	199
3	Turfing with lead watering and tamping ..	S.yd.	1386

M. A. SRINIVASACHARI,
Executive Engineer.